App.F.IX-4]

WD2239.B490.

1924.

File No. 302-24

Previous References.

(Immigrn)

Serial Nos. 1 — 2

Later references.

Estimates

9

GENERAL & REVENUE SECRETARIAT

Serial Nos. 2

Part B for May 1925

SUBJECT

Submit for sanction two estimates (Rs 210/- & Rs 621/-) for a masonry object case & a compound wall to the Dispensary Bungalow at Chamarajanagar.

C.S. No. 1731-2 dated 29.5.25

To the Secy. Com. & Comptr.

Enclosures

G. R. S III—1] 191 -25

GENERAL AND REVENUE SECRETARIAT.

(Mlg)

NOTES.

File No.

FILE HEADING.

Estimate for Rs 6594 for the construction of a nagar Khana and compound wall to the Akhalshah Kadri Dargah at Chennapatna.

From

The Mlg: Collr.

No. 1288 of 1925 Dated 16-5-25 Received 18/5

Diary No. 1779	Enclos. 1 file Spare Copies.	Serial No. 1

BRIEF ABSTRACT OF LETTER.

Forwards two estimates for Rs 210 & Rs 562 for two addl. works proposed to be executed in connection with the sanctd. estimate & states that the cost of these works will be met from the savings expected from the already sanctd. estimate.

NOTES AND ORDERS.

S

A revised estimate for the construction of a Nagar wall to the Ak. Shah. Chennapatna was sc. of 250-2/Mlg 8-23-4 L.S. 8.

NOTES—First Sheet.

Serial No.

being met from the funds at the credit of the distribution.

2 In the same letter is provision of Rs 10 for a bench soon this case. In lieu of this it is proposed to put up a resource of the cost being only Rs 10, the balance being saved thereby.

3 Again there is a provision at 39 in the estimate for a compound wall of 15 ft. this is stated to be insufficient and a compound wall to the north of 230 ft is proposed to be put up the cost is proposed to be met from savings of Rs 10 and also the estimated savings expected from the execution of estimate.

4. As nonrecurring cost is involved by the alterations of the two items in the estimate & the cost is proposed to be met from the savings to be effected in the working out of the cost work a draft sanctioning the two estimates is put up for approval.

SD
19.5.25

23 5 25.

583/28.5 (Ist member)

Approved

NOTE—Contn Sheet

Issue
26 5 25

Navy. File No 302 of 1924.

General and Revenue Secretariat.

Serial No. 2

To the Navy. Comm^{rs} & Comptroller. No. 1731-2 d. 29.5.25. Granting the Estimates for Rs. 2108 Rs. 562, the charge being met from the Savings expected from the "Works" amount.

NOTE—Contn. Sheet

4681

No. 1288/Mu-4 En file

Office of the Muzrai Commissioner in Mysore.

Dated Bangalore, 16th May 1925.

From

C. S. Balasundaram Iyer, Esquire., B.A.,
Muzrai Commissioner in Mysore,
Bangalore.

18 MAY 1925 MUZRAI
17 MAY 1925 G. D. SECTION

Dno 1779 Mug-30-4-1

To

The Secretary to the Government of
His Highness the Maharaja of Mysore,
Revenue Department.

ST 6/5

Sir,

With reference to Government Order No.250-2/Muz.8-23-4 dated 15th August 1923 sanctioning an estimate for Rs.6594/- for the ----- construction of a nagar Khana and compound wall to the Akhalshakadri Darga at Chennapatna I have the honor to forward the marginally noted --- estimates received from the Deputy Commissioner Bangalore District with his No.C.3-307-25 dated 26th April 1925 and to state that the Executive Engineer Bangalore ---- Division states in his letter to the Deputy Commissioner that the cost of Rs.210/- for item 1 may be met from the lump sum provision of Rs.350 provided in the sanctioned estimate for a teakwood stair case and that item 2 is also found necessary as the present provision for compound wall to a length of 15 feet only is insufficient and proposes the cost of this being met from the savings expected from the already sanctioned estimate for Rs.6594/-.

1. Masonry stair case in place of costly teak wood stair case	Rs.210/-
2. Putting up compound wall to a length of 230 ft. not included in the -- estimate.	Rs.562/-

Both the Executive Engineer and the Deputy Commissioner recommend that these two estimates might be sanctioned. In this circumstance I request that sanction may be accorded with the express instructions -- that this extra item of a longer compound wall should be completed --- entirely out of the savings to be effected in working out the sanctioned estimate.

The enclosures received with the Deputy Commissioners letter

are enclosed for reference and kind return.

I have the honor to be,

Sir,

Your most obedient servant,



For Muzrai Commissioner.

(Absent from station.)

Letter No.2166 dated Bangalore, 10th April 1925 from the Executive Engineer, Bangalore Division, to the Deputy Commissioner Bangalore District.

Nagarkhana at Chennapatna.

Reference:- G.O.No.250-2/Buz.2-29-4 dated 15-8-~~25~~ 23 sanctioning a revised estimate amounting to Rs.6594/- for the above work.

I have the honor to state that in the above revised estimate (herewith forwarded for reference and return) a lump sum provision of Rs.350/- for constructing a teak wood stair case has been made. During execution, it was found that in place of a costly teak wood stair case, a cheap brick masonry stair case similar to the one that exists in front of Syed Ibrahim Mohh may be put in and accordingly the work was put in hand. This costs Rs.210/- as per enclosed detailed estimate and plan.

Further, a provision is made in the revised estimate for constructing a compound wall for 15 feet only at a cost of Rs.30/- As large savings are expected from the sanctioned estimate amount and at present there is only a blind wall from the building to the road boundary, it is now proposed to put up a compound wall, as per detailed plan and estimate enclosed. This costs Rs.569/- and is proposed to be met out of the savings.

I request therefore that the above two estimates be countersigned and returned.

"COPY"

Deputy Commissioner,
Bangalore District.

G.R.S. VI G 34]

SUBJECT.....

.....

.....

Diary No. of letter replied to..... 1771.....

Section Aug.

File No. 361-14

Serial No.

General and Revenue Secretariat

(Rev)

, *the* *192* .

Proceedings of the Government of His Highness the Maharaja of Mysore

Date of issue.... 29.5.25

Signed by.... Mr T.R.

Read—

May this be

i Printed ?

ii treated as a standing order ?

iii published in the Gazette, English Part ?

iv translated ?

v placed at the disposal of the press ?

vi published in the Gazette, Kannada Part ?

Order Thereon No.

29/5/25

[illegible]

Inst. 1731-2/mur 302-24 - 2 Encl. One file
29.5.25

As the different items proposed in the same Estimate do not involve any extra cost, the two estimates for Rs 210 and Rs 562 are sanctd.

The Estimates for Rs 210 and Rs 562 are sanctd. The charges being met from the savings expected from the sanctd Estimate.

Copied by

Examined by

25/3

W.B.S. Secretary
Rev. Dept
20/5/25

To The Musy Commr, Retg the, ~~sanctd~~ estimates sanctd and dates enclos.
Compt to Govt.

WD 1888—GPB—1 000 00—21 12 21

ABSTRACT OF ESTIMATE FOR

constructing a compound wall left side in a line with the compound wall of a grave Mar[illegible]up to western boundary to join the same to the ruined grave yard wall of Nagarkhana at Channapatna

Particulars	Per	Rate	Quantity	Cost
1. Earth work excavation for foundation.	cyd	4	26	7-0-0
2. Rough stone in mud for foundation.	cft	2	690	36-0-0
3. Burnt brick in mud.	"	4	992	248-0-0
4. Plastering with mortar	sqr	3-0-0	23.00	69-0-0
5. Brick in mortar coping complete	Rft	10	230	144-0-0
6. Colour washing	sqr.	5	23.00	8-0-0
Total				562-0-0

Rupees five hundred and sixty two only.

* C O P Y *

S Srinivachar

Superintendent, Muzrai Branch.

(in charge)

Sanctioned for Rs.

No dated in Govt.Pros.

WD 0611 GPB 250-3 8-22

a modified

ABSTRACT OF ESTIMATE FOR

constructing a masonry stair case to Na, Arkkana at Charanatha. Mu: 50].

1. Earth work excavation for foundation.	cyd	4	2	1-0-0
2. Chunnam concrete	cft	4	64	10-0-0
3. Burnt brick in mortar	"	6	200	99-0-0
4. Plastering with mortar	sqr	1-8-0	7.00	11-0-0
5. Teakwood panelled door with hinges &c.	sft	7-8-0	18	45-0-0
6. Burnt stone slabs dressed and fixed.	"	8	70	35-0-0
7. Chacolate painting	sqr	5-0-0	0.30	1-5-0
8. White washing		L. S.		1-0-0
Total				210-0-0

Rupees two hundred and ten only.

* C O P Y *

Superintendent, Muzrai Branch.

(in charge)

Sanctioned for Rs.

No